

**AMENDMENT TO THE NORTH CENTRAL TEXAS PUBLIC WORKS CONSTRUCTION
STANDARDS, AMENDED FIFTH EDITION, AUGUST 2023**

DIVISION 300 ROADWAY CONSTRUCTION

ITEM 303 PORTLAND CEMENT CONCRETE PAVEMENT

303.5 Construction Materials

303.5.6.2 Hand

Delete the second sentence:

“The addition of one-sack of cement per cubic yard shall be required for all hand finish concrete.”